





3 FRONT ELEVATION (HIPOPTION)  
SCALE: 1/4" = 1'-0"



2 FRONT ELEVATION (SHED OPTION)  
SCALE: 1/4" = 1'-0"



1 FRONT ELEVATION (GABLE OPTION)  
SCALE: 1/4" = 1'-0"

## MATERIAL LEGEND

	HARDIE LAP SIDING WITH 6" CORNER BOARDS, PAINT
	40-YEAR ARCHITECTURAL ASPHALT SHINGLE ROOF, GAF-ELK OR APPROVED EQUAL
	STUCCO OVER FOUNDATION


## GENERAL NOTES

### NOTES:

1. INSTALL ALL SIDING AND ROOFING MATERIALS PER MANUFACTURERS RECOMMENDATIONS
2. INSTALL ROOFING OVER MFR RECOMMENDED UNDERLAYMENT or TITANIUM ROOF UNDERLAYMENT AND 3/4" PLYWOOD ROOF SHEATHING, UNLESS NOTED OTHERWISE
3. INSTALL SIDING OVER TYVEK HOUSE WRAP AND 1/2" PLYWOOD SHEATHING, UNLESS NOTED OTHERWISE
4. ALL EXTERIOR TRIM, INCLUDING DOOR AND WINDOW TRIM SHALL BE 5/4 HARDIE TRIM or WOOD SPECIES TO MATCH SIDING, SMOOTH SIDE OUT, PAINTED
5. PROVIDE METAL DRIP FLASHING OVER ALL HORIZONTAL TRIM, TYP



6 SIDE ELEVATION  
SCALE: 1/4" = 1'-0"



5 REAR ELEVATION  
SCALE: 1/4" = 1'-0"



4 SIDE ELEVATION  
SCALE: 1/4" = 1'-0"